

路面工程数量表

工程名称：2017年大兴区104国道（K13+500-K46+840）中修工程

第 2 页 共 3 页

序号	桩号		位置		处理宽度 米	处理长度 米	处理面积 平方米	面层		铣刨旧路		改性乳化沥青粘层 平方米	改性乳化沥青透层 平方米	备注
			进京	出京				5厘米ZAC-16C 平方米	7厘米ZAC-25C 平方米	5厘米 平方米	12厘米 平方米			
1	K33+400	K33+480	√		3.5	80	280	280		280		280		
2	K36+710	K36+800	√		3.5	90	315	315		315		315		
3	K44+086	K44+186	√		4.85	100	485	485		485		485		
4	K20+015	K20+065		√	3.5	50	175	175		175		175		
5	K20+150	K20+195		√	7	45	315	315	315		315	315	315	
6	K20+195	K20+250		√	4.5	55	247.5	247.5	247.5		247.5	247.5	247.5	
7	K20+700	K20+730		√	4	30	120	120		120		120		
8	K21+050	K21+150		√	3.5	100	350	350		350		350		
9	K21+210	K21+240		√	4	30	120	120	120		120	120	120	
10	K22+380	K22+500		√	3.5	120	420	420		420		420		
11	K22+880	K22+900		√	3.5	20	70	70	70		70	70	70	
12	K23+220	K23+270		√	4	50	200	200	200		200	200	200	
13	K23+610	K23+700		√	4	90	360	360		360		360		
14	K23+900	K23+970		√	4	70	280	280		280		280		
15	K24+000	K24+050		√	4	50	200	200		200		200		
16	K24+050	K24+130		√	3.5	80	280	280		280		280		
17	K24+560	K24+610		√	4	50	200	200	200		200	200	200	
18	K24+680	K24+730		√	4	50	200	200	200		200	200	200	
19	K24+730	K24+760		√	4	30	120	120	120		120	120	120	
20	K24+900	K25+000		√	4	100	400	400	400		400	400	400	
21	K25+200	K25+300		√	3.5	100	350	350		350		350		
22	K25+380	K25+400		√	4	20	80	80	80		80	80	80	
23	K25+780	K25+820		√	4	40	160	160		160		160		
24	K25+900	K25+950		√	4	50	200	200	200		200	200	200	
25	K26+500	K26+550		√	4.5	50	225	225		225		225		
26	K39+230	K39+280		√	4.6	50	230	230		230		230		
27	K39+560	K39+620		√	4.6	60	276	276		276		276		
28	K39+825	K39+968		√	4.6	143	657.8	657.8		657.8		657.8		
29	K40+961	K41+001		√	4.85	40	194	194		194		194		
30	K41+270	K41+295		√	4.5	25	112.5	112.5		112.5		112.5		
31	K41+860	K41+900		√	4.5	40	180	180		180		180		
32	K44+210	K44+250		√	4.85	40	194	194		194		194		
33	K44+430	K44+550		√	4.85	120	582	582		582		582		
34	K44+700	K44+735		√	7	35	245	245		245		245		
35	K45+619	K45+719		√	7.6	100	760	760		760		760		
36	K45+830	K45+930		√	7.7	100	770	770		770		770		
37	K46+200	K46+300		√	7.7	100	770	770		770		770		
38	K46+430	K46+530		√	4	100	400	400		400		400		
39							2000	2000		2000		2000		路口接顺
40							1000	1000	1000		1000	1000	1000	严重龟裂预留
41							1500	1500		1500		1500		一般龟裂预留
小计:							16023.8	16023.8	3152.5	12871.3	3152.5	16023.8	3152.5	
合计							22787.0	22787.0	4672.5	18114.5	4672.5	22787.0	4672.5	

编制:

复核:

审核:

